1.1 ADDENDUM

.1 The following changes to the specifications and drawings are to be incorporated in the Tender Documents.

1.2 CLARIFICATIONS

.1 Work related to the demolition & construction of the new aluminum windows “Type M”, shall be done in such way to not obstruct/reduce access via the main entrance of the building. Temporary protection / hoarding shall be provided to protect the surrounding areas.

.2 Access to the main entrance or entrance/exit from stairwells shall not be restricted during regular working hours (Monday to Friday, 8am to 5pm).

1.3 SPECIFICATIONS

.1 00 11 16 – Invitation to Tender

.1 Article 1.1.2: Revise the closing date to April 8th, 2020.

.2 Section 09 65 00 – Resilient Flooring

.1 Article 2.1.1.3: Replace “Marmorette / Linorette by Armstrong” with “DWL Landscape Collection, by Gerflor”.

.2 Delete Article 2.2.3

.3 Delete Article 3.1.7

1.4 ARCHITECTURAL DRAWINGS

.1 Drawing A-2, Detail 1

.1 For Rooms 201, 206 and 208 where there’s wall Type “B”, delete note “Add Sounds Attenuation Insulation In These Walls, Up To 12" Above Finished Ceiling”.

.2 Drawing A-4 – Notes:

.1 Add note 6. All existing window blinds on Lower Floor & Main Floor are to be remove and reinstall in locations where the glazing is to be replaced.

.3 Drawing A-6, Detail 1

.1 Add new floor & base to Corridor 204, type L3-Linolium with Rubber Base.

1.5 STRUCTURAL DRAWINGS

.1 Drawing L-2, Detail 2

.1 Steel lintel above new opening shall be a single steel angle, as shown on Detail 1, Sheet L-3

.2 Sills at new window openings shall be extruded aluminum sills, as shown on Detail 2, Drawing A-6

LICENSED ARCHITECT
LÉO B. GOGUEN
NOVA SCOTIA ASSOCIATION OF ARCHITECTS
2020-03-19

END OF SECTION