To all Bidders of Tender T-MCC-2005:

The following addendum applies to this Tender and must be taken into account when preparing a submission.

Section 00 74 00

Section 01 22 00 Measurement and Payment

Delete Subsection 9 and replace with the following:

9. Geotechnical Inspection

Unit of Measurement: Lump Sum (L.S)

This item includes: Provision of on-site inspection and testing by qualified geotechnical field personnel. All excavation, backfill, material placement, bedding, asphalt and concrete placement to be inspected. All inspections to be certified by a professional engineer (licensed to practice in NS) that the works completed are in accordance with the project specifications and industry standards.

Section 00 41 43

Delete Subsection 4 and replace with the following:

4. Schedule of Quantities and Unit Prices

ID	Description	Unit of Measurement	Estimated Quantity	Unit Price	Total Price
EARTHWORK					
3.0	Mass Excavation - Common	m^3	1000	$	$
8.0	Channel Construction	m	120	$	$
				Sub Total Earthwork	$
STORM SYSTEM					
31.1	300mm PVC DR35 Pipe	m	28	$	$
36.1	Connection to Existing Storm Pipe	each	1	$	$
37.1	1800mm Concrete Culvert	m	20	$	$
37.2	2100mm Concrete Culvert	m	7.5	$	$
37.3	2100mm Concrete Culvert Entrance	each	1	$	$
39.2	Pre-Cast Headwall (2100mm)	each	2	$	$
87.1	Rip Rap Lining (300-750mm)	m^2	1800	$	$
				Sub Total Storm System	$
SANITARY SYSTEM					
21.1	600mm Concrete Pipe	m	40	$	$
23.1	1200mm Manhole	each	1	$	$

23.3	1500mm Manhole	each	1	$	$
25.0	Connection to Existing	each	4	$	$
				Sub Total Sanitary System	$
STREET SYSTEM					
41.1	Type 1 Gravel	m^3	305	$	$
41.2	Type 2 Gravel	m^3	595	$	$
43.1	Asphalt Concrete Type C-HF	m^3	22	$	$
43.2	Asphalt Concrete Type B-HF	m^3	33	$	$
48.0	Guardrail	m	63	$	$
76.0	Street Signs	each	2	$	$
77.0	Crusher Dust Trail Extension	m	100	$	$
				Sub Total Street System	$
ADDITIONAL ITEMS					
9.0	Geotechnical Inspection	L.S.	1	$	$
10.0	Field Data Collection and Record Information	L.S.	1	$	$
78.0	Reconfiguration of Pedestrian Bridge/Walkway	L.S.	1	$	$
79.0	Repair of Existing Channel	L.S.	1	$	$
90.0	Environmental Measures	L.S.	1	$	$
				Sub Total Additional Items	$

SUMMARY

SUB TOTAL EARTHWORK $_____

SUB TOTAL STORM SYSTEM $_____

SUB TOTAL SANITARY SYSTEM $_____

SUB TOTAL STREET SYSTEM $_____

SUB TOTAL ADDITIONAL ITEMS $_____

ESTIMATED CONTRACT PRICE (EXCLUDING HST) $_____

ADD HARMONIZED SALES TAX (15%) $_____

TOTAL PRICE $_____

TENDERER'S HST REGISTRATION NO. _____

Delete Subsection 5 and replace with the following:

5. Completion Time

.1 Tenderer agrees to complete the Work within 8 weeks of the project start date of June 2, 2020. Work within the watercourse must comply with all rules and regulations set out by Nova Scotia Environment in the Watercourse Alteration Approval, including but not limited to the allowable construction duration set out in any granted extensions to the approval.

End of Addendum 2