To all Bidders of Tender T-MCC-2005:

The following addendum applies to this Tender and must be taken into account when preparing a submission.

The following questions were asked in relation to this tender.

Q1: What portion of the work is included in the rip rap quantity?
A1: The rip rap quantity includes rip rap lining of the constructed channel. Rip rap in plunge pools are included in the culvert line item.

Q2: What is the design thickness of the rip rap in the channel and plunge pools?
A2: All rip rap is to be 300-750mm diameter and shall be placed 750mm thick.

Drawing C-02 Culvert Plan & Profile 0+000 to 0+250

Add the following note:

'NOTE:

1. ALL RIP RAP SHALL BE PLACED MINIMUM 750 mm THICK, INCLUDING 300-750 mm Ø RIPRAP, 300-750mm RIP-RAP AND CLASS 2 RIP RAP.'

End of Addendum 3