PART 1 - GENERAL

1.1 Description

.1 This addendum forms an integral part of the specifications covering all aspects of work and is to be read in conjunction with the other documents. Should points arise which are at variance, the latest addendum will govern, unless clarified by the Engineer.

1.2 Purpose

.1 The purpose of this addendum is to amend the Tender Documents. This addendum includes:

- Pages: 1
- Tender Form Rev. 2

PART 2 – Clarifications

Please note the following clarifications:

1. Where there are references to topsoil and sod, please replace with topsoil and seed. This is correct in the tender form.

2. Reinstatement, after curb construction, has been covered under other items such as gravels and asphalt

3. Tender items 26 and 38, units have been changed from Each to m (see attached Tender Form Rev. 2).

4. Relocations of utility poles will be the responsibility of the Municipality. Item has been removed from the attached Addendum #1.

PART 3 – Closing Date

There will be no change to the closing date and time.

---------- END ADDENDUM #1 ----------

1. SALUTATION:

.1 To: Municipality of Cumberland
Upper Nappan Service Centre
1395 Blair Lake Road, Upper Nappan, NS, B4H 3Y4

.2 For: Princess Street Road Improvements
Springhill, Nova Scotia
Canada

.3 From: _____

2. TENDERER DECLARES:

.1 That this tender was made without collusion or fraud.

.2 That the proposed work was carefully examined.

.3 That the Tenderer was familiar with local conditions.

.4 That Contract Documents and Addenda No. ___ to ___ inclusive were carefully examined.

.5 That all the above were taken into consideration in preparation of this Tender.

3. TENDERER AGREES:

.1 To enter into a contract to supply all labour, material and equipment and to do all work necessary to construct the Work as described and specified herein for the unit prices stated in Subsection 4 hereunder, Schedule of Quantities and Unit Prices.

.2 That the Estimated Contract *Price* shall be the sum of the products of the tendered unit prices times the estimated quantities in Subsection 4 hereunder.

.3 That this Tender is valid for acceptance for sixty (60) days from Tender Closing.

.4 That measurement and payment for items listed in Subsection 4 hereunder shall be in accordance with corresponding items in Section 01 22 00 Measurement and Payment.

.5 To provide evidence of ability and experience within seven (7) days of request, including: experience in similar work, work currently under contract, senior supervisory staff available for the project, equipment available for use on the Work, and financial resources. The Owner reserves the right to reject any staff proposed for use on this project.

.6 To execute in triplicate the Agreement and forward same together with the specified contract security and insurance documents to the Owner within fourteen (14) days of written notice of award.

.7 That failure to enter into a formal Contract and give specified insurance documents and contract security within time required will constitute grounds for forfeiture of certified cheque or enforcement of bid bond.

.8 That if certified cheque is forfeited, Owner will retain difference in money between amount of Tender and amount for which Owner legally contracts with another party to perform the Work and will refund balance, if any, to Tenderer.

.9 That the Contract Documents include:

.1 Refer to Section 00 10 00 – Project Documents for a complete list of Contract Documents.

.10 That the work under this contract shall start as soon as possible. The Contractor shall mobilize on site within two (2) weeks from the date of award. A construction schedule shall be prepared to show a continuous and concentrated effort to complete the work. Close adherence to the schedule is a requirement of this Contract and coordination with Owner’s Personnel is a requirement of this Contract when establishing the schedule. Start-up shall also be contingent on receiving all pertinent approvals from regulatory authorities.

.11 That the Owner reserves the right to: reject all tenders or any tender; not necessarily accept the lowest tender; waive any irregularities, formalities, informalities or technicalities; and to accept or reject any offer whatsoever as considered by the owner to be in its best interest.

The Owner reserves the right to evaluate all aspects of a tender. The owner reserves the right to assess the Contractor’s and his Subcontractor’s capabilities to complete the work; to deliver a high quality built project; to complete the project on time and within the budget; and to assess these and other relevant factors along with price in selecting the contractor and defining the overall cost of the project.

The information provided in section Supplementary Tender Information will be used in making such evaluations. As such, the Contractor must provide complete and accurate Supplementary information. The Owner reserves the right to pursue leads arising from investigation of the supplementary information or request additional supplementary information from the contractor.

.12 Prior to submitting tender, Contractor to complete submission checklist attached at the end of this section.

4. SCHEDULE OF QUANTITIES AND UNIT PRICES

Item No.	Description	Unit of Measurement	Estimated Quantity	Unit Price	Total Price
EARTHWORK					
3.	Mass Excavation and Embankment - Common	m^3	750		
SANITARY SEWER SYSTEM					
21.	Pipe				
	.1 250mm dia. PVC	m	37		
23.	Manholes				
	.1 1050mm dia. Concrete	Each	3		
25.	Connections to Existing Main	Each	4		
26.	Closed Circuit Television Inspection	m	37		
STORM SEWER					
31.	Pipe				
	.1 150mm dia. PVC Perfo.	m	60		
	.2 150mm dia. PVC	m	8		
	.3 250mm dia. PVC	m	31		
	.4 375mm dia. PVC Culve.	m	8		
32.	Manholes				
	.1 1050mm dia. Concrete	Each	1		
33.	Catch Basins				
	.1 1050mm dia. Concrete	Each	1		
34.	Yard Catch Basins				
	.1 450x450mm Concrete	Each	1		
36.	Connections to Existing Main	Each	3		
38.	Closed Circuit Television Inspection	m	107		

STREET CONSTRUCTION

51.	Gravel				
	.1 75mm Type 1 (Road)	m^2	250		
	.2 200mm Type 2 (Road)	m^2	350		
	.3 150mm Type 1 (Sidewalk)	m^2	730		
53.	Asphalt Concrete				
	.1 50mm Type C	m^2	4850		
	.2 50mm Type B	m^2	250		
	.3 Mill 50mm Existing Asphalt	m^2	4600		
54.	Concrete Curb and Gutter				
	.1 Standard Curb	m	320		
	.2 Mountable Curb	m	500		
55.	Concrete Sidewalk				
	.1 100mm Thick	m^2	670		
63.	Re-grade/Reinstate Driveways	m^2	294		
64.	Relocate Signs	Each	3		
65.	New Signs				
	.1 Crosswalk	Each	4		
66.	Pavement Markings (cross Walks)	LS	100%		
67.	Tactile Plates	Each	21		

LANDSCAPING

71.	Topsoil and Seed	m2	1500		
76.	Tree Removal (Provisional)	Each	10		

ADDITIONAL ITEMS

80.	Trench Excavation - Rock (Provisional)	m^3	100		
81.	Trench Excavation –				

	Unsuitable Material (Provisional)	m^3	436		
82.	Replacement of Unsuitable Material with Selected Site Material (Provisional)	m^3	200		
86.	Traffic Control	LS	100%		

ENVIRONMENTAL PROTECTION

90I.	Silt Fence	LS	100%		
92I.	Straw or Hay Cover	LS	100%		

SUMMARY

SUB TOTAL EARTHWORK $_____

SUB TOTAL SANITARY SEWER SYSTEM $_____

SUB TOTAL STORM SEWER $_____

SUB TOTAL STREET CONSTRUCTION $_____

SUB TOTAL LANDSCAPING $_____

SUB TOTAL ADDITIONAL ITEMS $_____

SUB TOTAL ENVIRONMENTAL PROTECTION $_____

SUB TOTAL – CONTINGENCY $ 50,000

TOTAL SUMMARY

ESTIMATED CONTRACT PRICE
(EXCLUDING HST) $_____

ADD HARMONIZED SALES TAX (15%) $_____

TOTAL PRICE $_____

TENDERER'S HST REGISTRATION NO. _____

5. COMPLETION TIME

.1 Tenderer agrees to complete the Work within _____ weeks of written notification of award.

6. SIGNATURES*

DATED THIS _____ DAY OF _____ , 20 _____.

[Seal]

_____
Name of Firm Tendering

_____
Signature of Signing Officer

_____ _____
Witness Name and Title (Printed)

_____ _____
Witness Signature of Signing Officer

_____
Name and Title (Printed)

_____
Company Address

_____
Telephone No.

_____
Fax No.

*NOTE: Tenders submitted by or on behalf of any Corporation must be signed and sealed in the name of such Corporation by a duly authorized officer or agent.

7. SUPPLEMENTARY TENDER INFORMATION:

.1 List of Subcontractors:

._____.

._____.

._____.

._____.

._____.

._____.

List all subcontractors. The provision of the subcontractor list is an undertaking by the contractor to use the listed subcontractor on the project. Obtain the Engineer's approval to add or delete named subcontractors from the above list after the tenders have closed.

.2 List of all Equipment type that will be used on the project together with marked-up operated hourly rates including operator and also marked-up hourly labour rates - to assess resources applied to the project and establish charge-out rates if extra work is required.

Attach a separate sheet with this information

8. SUPPLEMENTARY INFORMATION

If requested, provide the following additional information prior to award.

.1 Financial references

.2 Project references - last three projects undertaken, plus two relevant projects complete with contact information

.3 List of material and equipment suppliers - incorporated into the work

.4 List of key personnel, title, experience

---------- END 00 41 43 ----------