MUNICIPALITY OF THE COUNTY OF CUMBERLAND

UV DISINFECTION UPGRADE

TENDER NO. T-MCC-2405

ADDENDUM NO. 2

July 25, 2024

(To be added to and made part of the Tender Documents)

The following changes or modifications shall be made to the Tender Documents:

TO THE SPECIFICATIONS

SECTION 00 21 31 - INFORMATION TO TENDERERS

Page 1, Item 2., delete **Friday, July 26, 2024** and replace with **Thursday August 1, 2024**.

TO THE DRAWINGS

DRAWING P01 – PIPING LAYOUT

Delete and replace NOTE 11 with:

11. ALL NEW PIPING TO BE 304L SS SCH10, JOINTS AND FITTINGS BE WELDED, FLANGED OR USING ROLL-GROOVED COUPLINGS WITH MATERIALS TO MATCH PIPING.

Add to NOTES:

13. INSULATE AND JACKET ALL NEW STAINLESS-STEEL PROCESS PIPING TO SPECIFICATIONS **SECTION 40 42 00.** WHERE EXISTING INSULATION OR JACKETING IS DAMAGED FROM PIPE REMOVAL AND RELOCATION, REINSTATE OR REPLACE WITH NEW.

14. CLEAN AND SWAB PIPING WITH MINIMUM 1% SODIUM HYPOCHLORITE AS A MEANS OF DISINFECTION TO MINIMIZE REQUIRED SHUTDOWN TIME. FLUSH AND COLLECT BACTERIA SAMPLES IN ACCORDANCE WITH AWWA STANDARD C651.

CBCL Limited
July 24, 2024
CBCL Project No. 230808.00