RFP-MCC-2427
Addendum #1

To All Bidders of RFP-MCC-2427:

Please note: the following addendum applies to RFP-MCC-2427 and shall be taken into consideration when preparing bid documents.

Q1: 3.2.1 Say installation by others. 1.1 of the RFP says supply and install. Can you clarify?

A: This RFP includes Supply and Installation.

Q2: Is this Automatic Transfer Switch to go outside or inside the building. We recommend inside. If outside, which Nema # do you want?

A: Automatic Transfer Switch to be mounted outside. Enclosure to be Nema 4X stainless steel.

Q3: 2.2.9.4 requires ammeter, voltmeter and alarm contacts. That type of charger is large and not offered from factory because it will not fit in the genset enclosure. We offer a sealed marine type 6 amp charger in its place. Volts are displayed and low volts alarm are displayed on the control panel. Will this be acceptable?

A: A 6 amp charger should be fine to meet the demand of the generator.

Q4: 2.2.6 requires 18 ka. I will need to use a 150 amp ATS to meet 18 ka. Our 100 amp switch is rated 14 ka, will this be acceptable?

A: 14ka is acceptable.

Closing Date: The closing date for this RFP has been moved to October 16, 2:00 PM.

A signed copy of each Addendum must also be included with the bid submission. Failure to include this Addendum may be cause for rejection. If you have any questions, please contact Shelby Hum at shelbyhum@cumberlandcounty.ns.ca

ALL OTHER SPECIFICATIONS, TERMS AND CONDITIONS REMAIN UNCHANGED.

Acknowledgement by Bidder:

Company Name: _____

Print Name: _____

Signed: _____

Date: _____

End of Addendum #1