CONTRACTOR TENDER FORM

Project #: T-MCC-2412
Name: Parrsboro Main St. Park

Closing Date: January 22, 2025 **Closing Time:** 2 PM

The Municipality of the County of Cumberland is currently accepting "tenders" from parties interested in:

The supply and installation of a Gravel Parking Lot at the Parrsboro Main St. Park. Gravel parking lot to be constructed per attached specifications, Schedule A, at the Parrsboro Main St. Park located at 4030 Eastern Ave. Parrsboro, NS. Construction must be completed by March 14, 2025.

Direct all questions and queries to:

Contact: Shelby Hum
Email: shelbyhum@cumberlandcounty.ns.ca

Issuing an Invitation implies no obligation on the Municipality of the County of Cumberland to accept any bid, or a portion of any Bid submitted. The lowest of any bid will not necessarily be accepted.

Pricing must include all fees and charges. **Pricing must exclude HST.**

CONTRACTOR QUOTE & COMPANY INFORMATION

Quote amount: $ _____

Company Name: _____

Contact Name: _____

Contact Number: _____

Signature: _____

Quotes can be:

E-mailed: procurement@cumberlandcounty.ns.ca
Delivered: Upper Nappan Service Centre,
1395 Blair Lake Rd. Upper Nappan, NS.

The Municipality of the County of Cumberland follows the Atlantic Standard Terms & Conditions for Goods and Services. Any discrepancy between this document and the Atlantic Standard Terms and Conditions; the Atlantic Standard Terms and Conditions shall prevail. Failure to comply with these Terms and Conditions could cause the Bidder's Bid to be disqualified.

Schedule A, Parrsboro Main St. Park Gravel Parking Lot

- Gravel Parking area 19m x 27m, 550m^2 total including driveway.
- Remove existing organics layer and unsuitable soils. Material can be used for rough grading around gravel area when complete.
- Place 200mm compacted Type 2 Gravel
- Place 150mm Type 1 Gravel – fine graded and compacted
- Grading around parking lot to be completed to provide proper drainage and prevent ponding.
- Landscaping at the edge of the completed gravel parking lot and driveway to make ready for seeding in the Spring.

150mm– BASE GRAVEL, TYPE 1

200mm – SUBBASE GRAVEL, TYPE 2



