RFP-MCC-2502
Addendum #2

To All Bidders of RFP-MCC-2502:

Please note: the following addendum applies to RFP-MCC-2502 and shall be taken into consideration when preparing bid documents.

Question: Can we change EPDM roof system from Elevate to Carlisle?

Answer: Yes. Carlisle roof system is acceptable.

Scope Changes:

- Change number of roof drains to two (2).
- Add two (2) vent stacks

Add the following roof system as an acceptable alternative:

- Remove existing roofing down to concrete decking and dispose at an approved facility
- Prime existing concrete deck with asphalt primer
- Install a torch on vapour barrier
- Install 2 layers of 2.6 Polyiso insulation with adhesive
- Install one layer of 3/16" of protection board with a laminated base sheet and secured with adhesive
- Install 2 roof drains
- Install 2 vents stacks
- Install new metal flashing

Bidders must indicate in their submission which roofing system is being proposed.

A signed copy of each Addendum must also be included with the bid submission. Failure to include this Addendum may be cause for rejection. If you have any questions, please contact Shelby Hum at shelbyhum@cumberlandcounty.ns.ca

ALL OTHER SPECIFICATIONS, TERMS AND CONDITIONS REMAIN UNCHANGED.

Acknowledgement by Bidder:

Company Name: _____

Print Name: _____

Signed: _____

Date: _____

End of Addendum #2