CONTRACTOR QUOTE FORM

Project #: RFQ-MCC-2514
Name: Off-Leash Dog Park

Closing Date: July 14, 2025 **Closing Time:** 2 PM

The Municipality of the County of Cumberland is currently accepting "quotes" from parties interested in: The supply and installation of a fully enclosed, off-leash dog park measuring 50 feet by 100 feet, to include a 5-foot-high chain-link perimeter fence, access gate, commercial dog waste receptacle, commercial dispenser for waste bags, a commercial bench, and all associated site preparation and cleanup. See **Schedule A** for additional details. Completion deadline: August 31, 2025. Must provide WCB and proof of liability insurance, comply with all applicable local building codes and safety regulations, and supply warranty details for all products and workmanship. ***Optional site visit for bidders on July 3 at 11 a.m.***

Direct all questions and queries to:

Contact: Shelby Hum
Email: shelbyhum@cumberlandcounty.ns.ca

Issuing an Invitation implies no obligation on the Municipality of the County of Cumberland to accept any bid, or a portion of any Bid submitted. The lowest of any bid will not necessarily be accepted.
Pricing must include all fees and charges. **Pricing must exclude HST.**

CONTRACTOR QUOTE & COMPANY INFORMATION

Quote amount: $ _____

Company Name: _____

Contact Name: _____

Contact Number: _____

Signature: _____

Quotes can be:

E-mailed: procurement@cumberlandcounty.ns.ca
Delivered: Upper Nappan Service Centre,
1395 Blair Lake Rd. Upper Nappan, NS.

The Municipality of the County of Cumberland follows the Atlantic Standard Terms & Conditions for Goods and Services. Any discrepancy between this document and the Atlantic Standard Terms and Conditions; the Atlantic Standard Terms and Conditions shall prevail. Failure to comply with these Terms and Conditions could cause the Bidder's Bid to be disqualified.

Schedule A

- Deliverables include completed installation of all elements listed, final walk-through and inspection with municipal staff, and as-built layout/sketch for records.

Site Preparation

- Clear designated park area (50’ x 100’) of any debris and rocks

Fencing & Gates

- Supply and install 5’ high chain-link fencing around the full perimeter (approximately 300 linear feet).
- Include a minimum of one gated entrance/exit.
- Gate must be self-closing and lockable.

Site Furnishings: Please provide manufacturer specs for site furnishings.

- 1 x commercial Bench for seating, must be durable and weather-resistant.
- 2 x commercial Dog Waste Bag Dispensers
- 2 x commercial Dog Waste Receptacles with secure lids and liners.
- 1 x commercial three-bin garbage, recycling centre.

Cleanup and Disposal

- Proper disposal of any waste materials and site cleanup post-installation.

Location

- Gateway Park, on Glooscap Trail Route 2 at the billboard site, 45.849395, -64.254639, Cumberland County, NS. https://maps.app.goo.gl/mNsbX9c7d2JLo9HEA
- Optional site visit for those bidding on July 3 at 11 a.m.
- Basic site plan concept follows.












WELCOME SIGNAL
SIX-PANEL KIOSK
ACCESSIBLE PATHWAYS
REPRESENTATION ONLY - NOT TO SCALE