CONTRACTOR QUOTE FORM

Project #: RFQ-MCC-2515
Name: Asphalt Crack Sealing and Sealcoating

Closing Date: July 14, 2025 **Closing Time:** 2 PM

The Municipality of the County of Cumberland is currently accepting "quotes" from parties interested in: The crack sealing and surface repair of approximately 1,300 linear feet of a municipal asphalt parking lot. The goal of this project is to prolong the life of existing pavement surface by sealing cracks and performing minor surface repairs, and sealcoating of entire surface to prevent further degradation due to weather and use. Completion deadline: August 31, 2025. Must provide WCB and proof of liability insurance, comply with all applicable local building codes and safety regulations, and supply warranty details for all products and workmanship. ***Optional site visit for bidders on July 3 at 11 a.m.***

Direct all questions and queries to:

Contact: Shelby Hum
Email: shelbyhum@cumberlandcounty.ns.ca

Issuing an Invitation implies no obligation on the Municipality of the County of Cumberland to accept any bid, or a portion of any Bid submitted. The lowest of any bid will not necessarily be accepted.
Pricing must include all fees and charges. **Pricing must exclude HST.**

CONTRACTOR QUOTE & COMPANY INFORMATION

Quote amount: $ _____

Company Name: _____

Contact Name: _____

Contact Number: _____

Signature: _____

Quotes can be:

E-mailed: procurement@cumberlandcounty.ns.ca
Delivered: Upper Nappan Service Centre,
1395 Blair Lake Rd. Upper Nappan, NS.

The Municipality of the County of Cumberland follows the Atlantic Standard Terms & Conditions for Goods and Services. Any discrepancy between this document and the Atlantic Standard Terms and Conditions; the Atlantic Standard Terms and Conditions shall prevail. Failure to comply with these Terms and Conditions could cause the Bidder's Bid to be disqualified.

Schedule A: Scope of Work

The scope includes, but is not limited to:

Surface Preparation
- Thorough cleaning of pavement surface and cracks
- Removal of any loose debris, vegetation, or foreign material.

Crack Sealing
- Routing (if required) and sealing of all visible longitudinal and transverse cracks ≥ 3mm (1/8") wide using hot-pour rubberized crack sealant.
- Use of professional-grade crack sealing compound meeting ASTM or equivalent standards.
- Ensure sealed cracks are level with the pavement surface and do not impede drainage.

Minor Surface Repairs (if required)
- Identify and patch potholes or severely degraded areas within the 1,300 ft stretch.
- Compact patch material to ensure smooth surface transition and prevent future failure.
- Areas requiring full-depth repair must be clearly identified and approved prior to work.

Sealcoating
- Application of black-top spray sealing (sealcoating) of entire paved surface.

Additional Notes:
- Measurements are approximate: bidders are responsible for confirming site conditions.
- Optional site visit may be arranged upon request.
- Traffic management (signage/cones/barricades) during work.
- All materials must be suitable for local climate and road conditions.
- Final inspection and sign-off with municipal staff is required at completion of project.
- ***Optional site visit for bidders on July 3 at 11 a.m.***

Location
- Gateway Park, on Glooscap Trail Route 2 at the billboard site, 45.849395, -64.254639, Cumberland County, NS. https://maps.app.goo.gl/mNsbX9c7d2JLo9HEA

