CONTRACTOR QUOTE FORM

Project #: RFQ-MCC-2517
Name: Accessible Pathways and Decorative Fire Hydrant Install

Closing Date: November 20, 2025 **Closing Time:** 2:00 PM

The Municipality of the County of Cumberland is currently accepting "Quotes" from parties interested in:

The construction of an accessible pathway from the existing parking area to the dog park gate at Gateway Park (21481 Highway 2, Fort Lawrence, NS) and constructing a connecting path from the driveway to the front edge of the kiosk pad to improve wheelchair accessibility. In addition, the Municipality seeks pricing to install a decorative "fire hydrant" feature within the dog park area. This feature is not connected to a water line and will serve as a thematic park element only. The "fire hydrant" will be provided by the Municipality with pick up location in Springhill.

Scope of work and quotation options follow in Schedule A.

Issuing an invitation implies no obligation on the Municipality of the County of Cumberland to accept any bid, or a portion of any Bid submitted. The lowest of any bid will not necessarily be accepted.

Pricing must include all fees and charges. **Pricing must exclude HST.**

CONTRACTOR QUOTE & COMPANY INFORMATION

Quote amount: $ _____

Company Name: _____

Contact Name: _____

Contact Number: _____

Signature: _____

Quotes can be:

E-mailed: procurement@cumberlandcounty.ns.ca
Delivered: Upper Nappan Service Centre,
1395 Blair Lake Rd. Upper Nappan, NS.

The Municipality of the County of Cumberland follows the Atlantic Standard Terms & Conditions for Goods and Services. Any discrepancy between this document and the Atlantic Standard Terms and Conditions; the Atlantic Standard Terms and Conditions shall prevail. Failure to comply with these Terms and Conditions could cause the Bidder's Bid to be disqualified.

Schedule A

Scope of Work

A. Accessible 1.6 m wide Pathway Construction x 2

The successful contractor will:

- Add a connecting path from the driveway to the front edge of the existing kiosk concrete pad and add a connecting path from the edge of the circular driveway to the entrance gate of the off-leash dog park.
- Ensure grading provides smooth transition between surfaces for wheelchair users.
- Excavate existing materials to a depth of 300 mm.
- Supply, place, and compact 150 mm of Type 2 gravel.
- Supply, place, and compact 100 mm of Type 1 gravel, graded to provide a firm base and positive drainage.
- Supply, place, and compact 50 mm of hot mix asphalt (asphalt option).
- Final area of work is approximately 43.4 square metres.

B. Decorative Fire Hydrant Installation

- Install one decorative fire hydrant (non-functional) securely mounted in a visible location within the dog park area.
- The feature will not be connected to any active water source.
- Hydrant will be supplied by the Municipality, with approximately 3’ deep base, with pick up location in Springhill. The Municipality will assistance with loading.

Quotation Options

Contractors are requested to provide pricing for three (3) surfacing options to meet CSA accessibility standards:

1. Option A – Gravel Surface Only:
    - Supply and compact Type 2 and Type 1 gravel to finished grade.
    - No asphalt or concrete top layer.
2. Option B – Asphalt Surface:
    - Full construction per specifications above (Type 2 + Type 1 + 50 mm hot mix asphalt).
3. Option C – Concrete Surface:
    - Full construction per specifications above with a concrete finish in lieu of asphalt.

Please provide individual pricing for each option, including materials, labour, equipment, and HST.

Optional Site Visit

A non-mandatory site visit can be arranged upon request by contacting Eileen Davage by phone at 902-664-6230.

Map

21481 Highway 2, Fort Lawrence, NS. Dimensions are approximate.

