REQUEST FOR QUOTATIONS
RFQ-MCC-1803
TO DECOMMISSION ABANDONED TEST WELLS
PUGWASH N.S.

Closing Date August 23, 2018 @ 2pm

municipality of cumberland

Upper Nappan Service Centre
1395 Blair Lake Rd.,
Upper Nappan, NS B4H 3Y4
Phone (902) 667-2313
Fax (902) 667-1352

Springhill Service Centre,
PO Box 1000,
Springhill, NS B0M 1X0
Phone (902) 597-3751
Fax (902) 597-3637

Parrsboro Service Centre,
4030 Eastern Ave, Box 400
Parrsboro, NS, B0M 1S0
Phone (902) 254-2036
Fax: (902) 254-2313

Municipality of Cumberland
Terms of Reference
Decommissioning of wells

1.0 Introduction

The Municipality of the County of Cumberland (the Municipality) is soliciting quotations for the decommissioning of abandoned test wells in Pugwash, NS: area.

2.0 Scope of Work

All work to be done in accordance with the Water Well decommissioning Guidelines published June 1, 2007 by Nova Scotia Environment and labor, see attached, with the following additional requirements

- Wells to be filled with course grade bentonite (3/8" or greater) with finer material screened out before pouring pellets into the well.
- Cut off metal casing 0.5 meter below grade
- Level site with local material
- Repair any damage to site

3.0 6" Wells to be decommissioned

				GPS LOCATION		
			DEPTH	north	west	location
1	Carter	CP1A	270	45 49 14.50	63 41 54.74	off Pugwash River Road
2	Carter	CP2A	320	45 49 26.94	63 42 21.18	off Pugwash River Road
3	Carter	CP3A	300	45 49 39.50	63 42 44.93	off Pugwash River Road
4	Carter	CP4A	340	45 49 23.55	63 42 24.47	off Pugwash River Road
5	Chase	1	300	45 48 21.88	63 44 09.51	Old Murray Road near production well 3
6	Neaves	N1	340	45 51 30.94	63 35 37.84	off Irishtown Woods Road

municipality of cumberland

Upper Nappan Service Centre
1395 Blair Lake Rd.,
Upper Nappan, NS B4H 3Y4
Phone (902) 667-2313
Fax (902) 667-1352

Springhill Service Centre,
PO Box 1000,
Springhill, NS B0M 1X0
Phone (902) 597-3751
Fax (902) 597-3637

Parrsboro Service Centre,
4030 Eastern Ave, Box 400
Parrsboro, NS, B0M 1S0
Phone (902) 254-2036
Fax: (902) 254-2313

4.0 SUBMISSION REQUIREMENTS

a. Provide lump sum price to carry out this work to decommission all 6 wells as identified
b. Provide evidence of experience in similar work
c. Provide Proof of certification by the N S worker's compensation board if eligible.
e. Provide certification of good standing with the N S Construction Safety Association if eligible.
f. Provide proof of minimum of $2,000,000 general liability insurance coverage

5.0 PRE-PROPOSAL QUESTIONS

Contractors are to submit written questions by email to:
Ron Patterson cell 902-664-7044
ronspat@outlook.com

6.0 PROPOSAL SUBMISSION:

Justin Waugh-Cress, P. Eng.
The Municipality of the County of Cumberland
1395 Blair Lake Road
Upper Nappan, NS B4H 3Y4