

**T-MCC-2103**  
**SHINIMICAS FIRE DEPARTMENT BUILDING**

**Addendum #5**

Please see attached Engineers letter dated May 11, 2021 for clarifications to the tender document:

May 11, 2021

John H Baxter, P.Eng.  
925 Route 970  
Baie Verte, NB  
E4M 1Z6

506 381 4809 cell  
jbaxter@baxterengineeringltd.com

Kellie Seaman  
Municipality of Cumberland  
Upper Nappan Service Centre

**Re: Tender for New Shinimicas Fire Hall Building – Clarifications & Corrections, May 11-21**

Dear Kellie:

*The following are some further clarifications to the tender documents based on questions received. These are supplemental or additional to those included in my letters of April 15 & Apr 27, 2021.*

*All temporary and final electrical service connections and permitting are the responsibility of the contractor.*

*Electrical service meter socket is to meet the current NS Power requirement.*

*Communications panel is to be located in the Training Room on W6 wall near the door to Fire Truck Bays. W6 is 2hr fire rated-any equipment must be surface mounted with proper protection.*

*A floor drain with trap primer is to be added in Storage Rm 1 in the Training Room area.*

*Washroom showers are to also include trap primers on the drains.*

*All painting is the responsibility of the contractor. A quality specification for paint as PPG Manor Hall or equal was included in the April 15-21 letter. Primer is to be of similar quality.*

*Please let me know if any further questions come up.*

Sincerely,

  
John H Baxter, M.A., P.Eng.

End of Addendum #5